

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-21517-00-02
Spot: SWNE Sec/Twnshp/Rge: 31-16S-29W
3260 feet from S Section Line, 1800 feet from E Section Line
Lease/Unit Name: DICKEY I Well Number: 1
County: LANE Total Vertical Depth: 4600 feet

Operator License No.: 31627
Op Name: WHITETAIL CRUDE, INC
Address: 201 WASH PO BOX 544
NESS, KS 67560

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 308 WITH 190 SX CMT
Production: Size 4.5 feet: 4599 WITH 225 SX CMT
Liner: Size feet: 149.50

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/22/2000 11:15 AM

Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.

Proposal Rcvd. from: MIKE FRITZLER Company: WHITETAIL CRUDE Phone: (785) 798-3641

Proposed Plugging Method: PUMP DOWN 8 5/8 X 4 1/2 ANNULUS WITH 50 SX CMT IF NEEDED. PUMP DOWN 4 1/2 CASING 200# HULLS 60 SX CMT WITH 200# HULLS MIXED IN. PUMP 10 SX GEL & 130 SX CMT. SHUT IN. CHECK CMT TOP AND TOP OFF IF NEEDED.

Plugging Proposal Received By: MICHAEL MAIER
Date/Time Plugging Completed: 12/22/2000 12:15 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)
KCC Agent: KEVIN STRUBE

Actual Plugging Report:

DV @ 2248' WITH 500 SX CMT. PERFS AT 4238-41, 4518-21, 4510-12'. PUMPED DOWN 8 5/8" X 4 1/2" ANNULUS 1 BBL WATER. PRESSURED TO 500# SHUT IN. PUMPED DOWN 4 1/2" CASING 200# HULLS, 60 SX CMT WITH 200# HULLS MIXED. PUMP 10 SX GEL & 130 SX CMT. WELL ON VACUUM. SHUT IN. WILL COME BACK LATER & CHECK CMT TOP & TOP OFF IF NEEDED.

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 02 2001

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

01-02-2001
CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed

Kevin A. Strube

(TECHNICIAN)

DEC 28 2000

113100
2001061235 MP

[Signature]
FORM CP 2/3