

To: 1 290308 7-30  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,720-00-01  
NW NW SW, SEC. 18, T 16 S, R 29 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 3988

Operator: Slawson Exploration Company, Inc.  
Name & Address: 104 S. Broadway  
Wichita, KS 67202

2310 feet from S section line  
4950 feet from E section line

Lease Name Magie Well # 1-18

County Lane 14.39

Well Total Depth 4443 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 360

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 8:30 a.m. Day: 30 Month: 7 Year: 19 93

Plugging proposal received from David Brady

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 4420' w/175 sx cement, TOC 3586', PBTD 4376', Perfs at 4301-04', Port Collar at 2325'

1st plug set CIBP at 4275' with 2 sx cement on top,

2nd plug pump 50 sx cement at 2250', 3rd plug pump 80 sx cement at 1230-40',

4th plug pump 25 sx cement at 690', 5th plug pump 50 sx cement at 400', 6th plug pump 10 sx cement at 40-0'.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:45 p.m. Day: 30 Month: 7 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4275' with 2 sx cement on top,

2nd plug shot pipe at 2380', pulled 4 jts. to 2250', spotted 50 sx cement,

Pipe stuck, shot at 1800', pipe stuck, shot at 1300', pipe stuck, shot at 1200',

3rd plug pumped in 80 sx cement at 1200',

Pipe stuck, shot at 900', pipe free, 4th plug pulled to 680' and spotted 25 sx cement,

5th plug pulled to 400' with 50 sx cement, 6th plug at 40' with 10 sx cement

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 900' of 4 1/2" casing.

Additional description is necessary, use BACK of this form.

INVOICED

(did / observe this plugging.

DATE: 8-12-93

INV. NO. 38322

Signed \_\_\_\_\_ (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION 08-10-1993 AUG 10 1993