

To: 1 071036
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

3-30

API NUMBER 15- 101-21,029-0000 *R214*

SW SW SE, SEC. 18, T. 16 S, R. 29 W/E
330 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 6040
Operator: Bankoff Oil Company
Name & Address: 6202 S. Lewis, Suite 176
P.O. Box 700657
Tulsa, OK 74170

Lease Name Magie Well # 2
County Lane 145.60
Well Total Depth 4480 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 334

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 3:30 p.m. Day: 30 Month: 3 Year: 19 92

Plugging proposal received from Mike Kelso
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 4479' w/120 sx cement. Perfs at 4295-4300'
1st plug sand back to 4240' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 50 sx cement at 2190', 3rd plug pump 80 sx cement at 1200',
4th plug pump 50 sx cement at 360', 5th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 7 p.m. Day: 30 Month: 3 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4240' and dumped 5 sx cement on top of sand through bailer,
2nd plug shot casing at 1200' and spotted 40 sx cement,
3rd plug shot casing loose at 800' and spotted 40 sx cement,
4th plug pulled casing to 360' and spotted 40 sx cement,
5th plug pulled casing and topped off with 20 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied. Recovered 800' oil casing.
(If additional description is necessary, use BACK of this form.)
I (did/observe) observe this plugging.

INVOICED
DATE 4-8-92
INV. NO. 54896

Signed *Dan Jordan* (TECHNICIAN)

STATE CORPORATION COMMISSION
RECEIVED
APR 10 1992
CONSERVATION DIVISION
WICHITA, KANSAS