

To: 1 170151
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,051-00-00
NW SW NW, SEC. 21, T16 S, ~~R~~ 29 W/E
3630 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5131
Operator: Thunderbird Drilling, Inc.
Name & Address: P. O. Box 97
Ellinwood, KS 67526

Lease Name Jennison "C" Well # 1
County Lane 148.53
Well Total Depth 4570 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 266

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Thunderbird Drilling, Inc. License Number 5131
Address P. O. Box 97, Ellinwood, KS 67526

Company to plug at: Hour: 11:00 am Day: 14 Month: March Year: 19 86

Plugging proposal received from Earl Cooper
(company name) Thunderbird (phone) 316-564-2577

were: 5 1/2" at 4510' PBTD 4181' Perfs at 4166-4174' 450 sx cement through stage collar at
1st plug sand back to 1830' and dump 4 sx cement on top of sand through bailer
2nd plug squeeze well with 1 sack hulls, 30 sx cement, 10 sx gel, 50 sx cement, 8 sx gel,
1 sack hulls, release 5 1/2" rubber plug and pump 100 sx cement.

Plugging Proposal Received by James R. Kapp
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None
Operations Completed: Hour: 11:45 am Day: 14 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 1830' and dumped 4 sx cement on top of
sand through bailer, 2nd plug squeezed well with 1 sack hulls, 30 sx cement, 10 sx gel,
50 sx cement, 8 sx gel, 1 sack hulls, released 5 1/2" wiper plug and pumped 100 sx cement.
Cement fell to 800' - 3-18-86 - Pumped 90 sx cement to surface. Completed at 2:00 pm

Maximum pressure 0 - Vac.

Remarks: No recovery. Used 60/40 Pozmix 6% gel by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging
STATE CORPORATION COMMISSION

DATE MAR 20 1986
INV. NO. 13039
3-14

MAR 20 1986
03-20-1983
CONSERVATION DIVISION
Wichita, Kansas

Signed Dan Jordan
(TECHNICIAN)