

1 120018
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

9-24-87
API NUMBER 15- 101-21,418 -00-00
NW SE SE, SEC. 21, T 16 S, R 29 W/E
990 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5063
Operator: Energy Exploration, Inc.
Name & Address: 1002 South Broadway
Wichita, KS 67211

Lease Name Pam Well # 1
County Lane 149.83
Well Total Depth 4610 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 280

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SMD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor H-30 Drilling, Inc. License Number 5107
Address 251 North Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 3:30 p.m. Day: 24 Month: 9 Year: 19 87

Plugging proposal received from Rick Davis
(company name) H-30 Drilling, Inc. (phone) 316-263-2043

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2247' Elevation 2805'
1st plug at 2247' with 50 sx cement, 2nd plug at 1420' with 100 sx cement,
3rd plug at 310' with 50 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:30 p.m. Day: 24 Month: 9 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2250' with 50 sx cement,
2nd plug at 1425' with 100 sx cement,
3rd plug at 310' with 50 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
09-29-1987
SEP 29 1987

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED
Please observe this plugging.

Signed Quinn Rankin (TECHNICIAN)

DATE 10-6-87
INV. NO. 18383