

To: 1 190361 10-5  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-101-21,747-00-00  
S/2 NE SE, SEC. 21, T 16 S, R 29 W/EX  
1650 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License / 3447  
Operator: Ranken Energy Corp.  
Name: 601 N. Kelly, Ste. 103  
Address: Edmond, OK 73003-4855

Lease Name Miller Well # 1-21  
County Lane 150.80  
Well Total Depth 4640 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 206.88

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A  X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Discovery Drilling License Number 31548  
Address P.O. Box 763, Hays, KS 67601

Company to plug at: Hour: 6:30 a.m. Day: 5 Month: 10 Year: 1997

Plugging proposal received from Tom Alm  
(company name) Discovery Drilling (phone) 785-623-2920

Work: to fill hole with heavy mud and spot cement through drill pipe  
1st plug at 2246' with 50 sx cement, 2nd plug at 1200' with 80 sx cement,  
3rd plug at 600' with 40 sx cement, 4th plug at 230' with 40 sx cement,  
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,  
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)


Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None  X

Operations Completed: Hour: 9:30 a.m. Day: 5 Month: 10 Year: 1997

ACTUAL PLUGGING REPORT 1st plug at 2246' with 50 sx cement,  
2nd plug at 1200' with 80 sx cement, 3rd plug at 600' with 40 sx cement,  
4th plug at 230' with 40 sx cement,  
5th plug at 40' with 10 sx cement, 10-08-1997  
6th plug to circulate rathole with 15 sx cement,  
7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.  
(If additional description is necessary, use BACK of this form.)

UNVOICED observe this plugging.

Signed  (TECHNICIAN)

DATE  
INV. NO. 49289