

1060382

API NUMBER ²¹⁰⁶⁵ 15-101-21,064-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW SW NE, SEC. 28; T 16 S, R 29 W/E
3630 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name Richards 'I' Well # 6

Operator: Donald C. Slawson

County Lane

Name & Address 200 Douglas Building

Well Total Depth 4635 ^{150.6'} feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 363

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Slawson Drilling, Inc. License Number 5657

Address 200 Douglas Building, Wichita, KS 67202

Company to plug at: Hour: 9:00 am Day: 26 Month: October Year: 19 84

Plugging proposal received from Glen Conway

(company name) Slawson (phone) 316-263-3201

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2200' with 50 sx cement

2nd plug at 1350' with 50 sx cement

3rd plug at 410' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement
Plugging Proposal Received by Paul A. Luthin

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 11:15 am Day: 26 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2200' with 50 sx cement, 2nd plug at 1350' with 50
sx cement, 3rd plug at 410' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -
plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with
10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

OCT 31 1984
10-31-1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton
(if additional description is necessary, use BACK of this form.)

I (operator) did (not) observe this plugging.

Signed Paul A. Luthin
(TECHNICIAN)

DATE 11-7-84

REV. NO. 4691
10-26