

To: 1 030693
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,442-00-00

NW NE SE, SEC. 25, T 16 S, R 29 (W) 15
2310 feet from S section line

990 feet from E section line

Lease Name James "E" Well # 1

County Lane 150.15

Well Total Depth 4620 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 330

TECHNICIAN'S PLUGGING REPORT

Operator License # 5144

Operator: Mull Drilling Co., Inc.

Name & Address P. O. Box 2758

Wichita, KS 67201

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Mull Drilling Co., Inc. License Number 5144

Address P. O. Box 2758, Wichita, KS 67201

Company to plug at: Hour: 10:00 am Day: 24 Month: April Year: 19 86

Plugging proposal received from Jerry Roane

(company name) Mull (phone) 913-798-3146

were: 4 1/2" at 4611' Perfs at 4555-4559'; 4548-4552'

1st plug set CIBP at 4360' with 2 sx cement

2nd plug sand back to 4300' and dump 2 sx cement on top of sand through bailer

3rd plug squeeze well with 100 sx cement

Pump 60 sx cement down annulus

Plugging Proposal Received by Don Ubel & Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 10:50 am Day: 24 Month: April Year: 19 86

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4360' with 2 sx cement, 2nd plug sanded back to 4300' and dumped 2 sx cement on top of sand through bailer, 3rd plug squeezed well with 100 sx cement, 4th plug pumped 60 sx cement down annulus.

Perforated at 1400' Block squeeze

Remarks: No recovery. Used Econolite cement by Halliburton.
(if additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION
APR 28 1986
04 28 1986
CONSERVATION DIVISION
Wichita, Kansas

INVOICED (if not) observe this plugging.

DATE APR 29 1986

Signed Steve Durrant
(TECHNICIAN)

INV. NO. 13610