

1 060733

API NUMBER 15-101-21,246-00400

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C-1/2 NE/4 SEC. 24, T 16 S, R 29 W1/4
3960 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5405
Operator: Oil Capital Corp.
Name:
Address Suite 530 Farmers & Bankers Bldg.
Wichita, Kansas
67202

Lease Name Gamet Well # 2-A
County Lane 152.10
Well Total Depth 4580 Mississippi feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 330341

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated Subdrill 2170' Elevation 2751

Plugging Contractor H-30 Drilling Inc. License Number 5107

Address 251 N Water, Suite 10 Wichita, Kansas 67202

Company to plug at: Hour: 7:00 PM Day: 23 Month: November Year: 1985

Plugging proposal received from Gary Pugh

(company name) H-30 (phone) 316-263-2043

were: 1st plug @ base of subdrillite w/ 50 sbx cement. 2nd plug @
Cheyenne w/ 80 sbx cement. 3rd plug @ 30' below base of surface
casing. 4th plug @ 40' on solid bridge & wood plug w/ 10 sbx cement.
Circulate 15 sbx cement in rat hole.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 9:30 PM Day: 23 Month: November Year: 1985

ACTUAL PLUGGING REPORT Cement was pumped through drill pipe w/
hole full of heavy mud. 1st plug @ 2157' w/ 50 sbx cement.
2nd plug @ 1500' w/ 80 sbx cement. 3rd plug @ 330' w/ 50 sbx
cement. 4th plug @ 40' on solid bridge & wood plug w/ 10 sbx cement.
filling hole to 0'. 5th plug circulated rat hole through
one joint of drill pipe w/ 15 sbx cement.

Remarks: B.G. Luten pumped 60/40 mix w/ 6% gel.
(If additional description is necessary, use BACK of this form.)

INVOICED Observe this plugging.

DATE DEC 10 1985

INV. NO. 11365

DEC 10 1985
12-02-1985
CONSERVATION DIVISION
Wichita Kansas

Signed Paul A. Luthi
(TECHNICIAN)

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date Nov. 19, 1985
month day year

API Number 15- 101-21,246-00280

OPERATOR: License # 5405
Name Oil Capital Corporation
Address Suite 520 Farmers & Bankers Bldg.
City/State/Zip Wichita, Ks. 67202
Contact Person Neil H. Sikes
Phone 262-2944

C. W/2 NE/4 Sec. 24 Twp. 16 S. Rg. 29 East
3960 West
Ft. from South Line of Section
1980 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5107
Name H-30 Drilling Inc
City/State Wichita, Ks.

Nearest lease or unit boundary line 660 feet
County Lane
Lease Name James Well # 2-A
Ground surface elevation 2751 feet MSI
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Surface pipe by Alternate: 1 2 X
Depth to bottom of fresh water 100'
Depth to bottom of usable water 1100'
Surface pipe planned to be set 300'
Projected Total Depth 400 feet
Formation Mississippi

Well Drilled For: Well Class: Type Equipment:
X Oil SWD Infield X Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl Wildcat Cable

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

cementing will be done immediately upon setting production casing.

Date 11-13-85 Signature of Operator or Agent Neil H. Sikes Title President

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required feet per Alt. 2

This Authorization Expires 5-4-86 Approved By 11-4-85

11-13-85 set 300' of 8 1/4"

STATE OF KANSAS
12-02-1985
DEC 2 1985