

1 050496

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,135-00-00

SE SW SW, SEC. 24, T 16 S, R 29 W/X

330 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5405

Lease Name Eaton Well # 1Operator: Oil Capital Corp.County Lane 150.48

Name &
Address 520 Farmers & Bankers Building
Wichita, KS 67202

Well Total Depth 4630 feetConductor Pipe: Size feetSurface Casing: Size 8 5/8 feet 352Abandoned Oil Well Gas Well Input Well SWD Well D&A xOther well as hereinafter indicated Plugging Contractor Abercrombie Drilling, Inc. License Number 5422Address 801 Union Center, Wichita, KS 67202Company to plug at: Hour: 2:00 am Day: 29 Month: March Year: 19 85Plugging proposal received from Harvey Moore(company name) Abercrombie (phone) 316-262-1841were: to fill hole with heavy mud and spot cement through drill pipe1st plug at 2220' with 50 sx cement2nd plug at 1100' with 50 sx cement3rd plug at 510' with 70 sx cement
solid bridge4th plug hulls - plug at 40' -- cement to surface with 10 sx cement6th plug to circulate rat hole with 10 sx cement, 7th plug to circulate mouse hole with
10 sx cement. Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)Plugging Operations attended by Agent?: All Part None XOperations Completed: Hour: 3:45 am Day: 29 Month: March Year: 19 85ACTUAL PLUGGING REPORT 1st plug at 2220' with 50 sx cement, 2nd plug at 1100' with 50sx cement, 3rd plug at 510' with 70 sx cement, 4th & 5th plugs - solid bridge - hulls -plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with10 sx cement, 7th plug to circulate mouse hole with 10 sx cement. STATE CORPORATION COMMISSION

APR 12 1985

04-12-1985

CONSERVATION DIVISION
WICHITA, KANSASRemarks: Used 60/40 Pozmix 2% gel 3% cc by Sun

(If additional description is necessary, use BACK of this form.)

INVOICED

(If not observed, do not observe this plugging.)

DATE 4-17-85Signed Richard W. Lacey
(TECHNICIAN)INV. NO. 2756