

1 110005

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,776-00-00

NW SE NW, SEC. 23, T 16 S, R 29 W/E

3630 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Lease Name Yates Well # 1

Operator: Chief Drilling Co., Inc.

County Lane 148.82

Name & Address 905 Century Plaza

Well Total Depth 4579 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 290

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 3:12 pm Day: 18 Month: September Year: 19 85

Plugging proposal received from Vernon Duntz

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4315' Perfs at 4257-4260', 4233-4236', 4184-4188'

1st plug sand back to 3130' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:10 pm Day: 18 Month: September Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 3130' and dumped 4 sx cement on top of sand through bailer. 2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

Maximum pressure 400 psi and shut in 150 psi

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2600' 4 1/2" casing. (if additional description is necessary, use BACK of this form.)

INVOICED RECEIVED observe the STATE CORPORATION COMMISSION

DATE 9-30-85

INV. NO. 10288

SEP 27 1985 09-27-1985 CONSERVATION DIVISION Wichita, Kansas

Signed James R. Karp (TECHNICIAN)