

1 030439

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,259-00-01
SE SE SE, SEC. 9, T 17 S, R 27 W/E

330 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5783

Lease Name Selfridge Well # A-3

Operator: Galloway Drilling Co., Inc.

County Lane 150.54

Name & Address 340 Broadway Plaza

Well Total Depth 4632 feet

105 South Broadway

Conductor Pipe: Size feet

Wichita, KS 67202

Surface Casing: Size 8 5/8 feet 336

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 12:00 pm Day: 18 Month: June Year: 19 85

Plugging proposal received from Ron Hoover

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4624' PBD 4555' Perfs at 4565-4569, 4558-4560, 4542-4545, 4547-4552'

1st plug sand back to 4500' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and 175 sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:20 pm Day: 18 Month: June Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4500' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 175 sx cement.

STATE CORPORATION COMMISSION

JUN 21 1985

Remarks: Recovered 2740' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

Jan Goddard observed the plugging
 observe this plugging.

Signed Steve Demont
(TECHNICIAN)

INVOICED

DATE 6-24-85

INV. NO. 8668

6-18