

To: 1 07:08915-101-20 232-00-00
ST. TE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 7/16/77

NW NW NE, SEC. 8, T 17 S, R 27 W/E
4950 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5383
Operator: A.L. Abercrombie, Inc.
Name &
Address Rt. 1, Box 56
Great Bend, KS 67530

Lease Name Johnson Well # 1
County Lane Lane 148.36
Well Total Depth 4565 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 242

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524-0347

Company to plug at: Hour: 3:15 p.m. Day: 28 Month: 8 Year: 19 92
Plugging proposal received from Mike Kelso
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 4544' w/250 sx cement. Parfs at 4151-57'
1st plug sand back to 4100' and dump 4 sx cement on top of sand through bailer,
2nd plug shoot pipe at 1300', pump 50 sx cement, 3rd plug shoot pipe at 80', pump 50 sx cement,
4th plug pull pipe to 250' and pump 40 sx cement,
5th plug pull pipe out and top off with 10 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 5:20 p.m. Day: 28 Month: 8 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4100' and dumped 4 sx cement on top of sand through bailer,
2nd plug shot pipe at 1300' and pumped 50 sx cement,
3rd plug shot pipe at 800' and pumped 50 sx cement,
4th plug pulled pipe to 250' and pumped 40 sx cement,
5th plug pulled pipe out and topped off with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 800' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (and others) observe this plugging.

INVOICES
DATE 9-14-92
CITY NO. 36143

Signed Dan Goodrow
(TECHNICIAN)

RECEIVED
ST. TE CORPORATION COMMISSION
SEP 2 1992
CONSERVATION DIVISION
Wichita, Kansas