

10-13-87

To: 1 070442  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,426 -00 -00

SE SW NE, SEC. 7, T 17 S, R 27 W ~~AK~~

2970 feet from S section line

1640 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name Hanks "R" Well # 2

Operator: Donald C. Slawson  
Name & Address: 200 Douglas Building  
Wichita, KS 67202

County Lane 152.10

Well Total Depth 4680 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 242

Abandoned Oil Well Gas Well Input Well SWD Well O&A X

Other well as hereinafter indicated

Plugging Contractor Slawson Drilling Company License Number 5657

Address 200 Douglas Building, Wichita, KS 67202

Company to plug at: Hour: 8 p.m. Day: 13 Month: 10 Year: 19 87

Plugging proposal received from Bob Rowe

(company name) Slawson Drilling Company (phone) 316-792-3356

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2126-65' Elevation 2722' GL

1st plug at 2130' with 50 sx cement, 2nd plug at 1320' with 80 sx cement,

3rd plug at 270' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None

Operations Completed: Hour: 11:30 p.m. Day: 13 Month: 10 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2130' with 50 sx cement,

2nd plug at 1320' with 80 sx cement,

3rd plug at 270' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

OCT 21 1987

Remarks: Used 60/40 Pozmix 6% gel by Allied. (if additional description is necessary, use BACK of this form.)

INVOICED

(if desired, please observe this plugging.)

DATE 10-22-87

Signed Dan Gooden (TECHNICIAN)

INV. NO. 18628

10-13

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date... October 6, 1987

API Number 15- 101-21,426-0002

OPERATOR: License # 5181
Name SLAWSON, DONALD C.
Address 200 Douglas Building
City/State/Zip Wichita, Kansas 67202
Contact Person Bill Horgan
Phone (316) 263-3201

SE SW NE Sec. 7 Twp. 17S S. Rg. 27 East
2970' Ft. from South Line of Section
1640' Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 330' feet
County Lane

CONTRACTOR: License # 5657
Name Slawson Drlg. Co.
City/State Wichita, Kansas

Lease Name HANKS 'R' Well # 2
Ground surface elevation 2722' GR (Sea) feet MSL

Well Drilled For: Well Class: Type Equipment:
Oil Storage Infield Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl Wildcat Cable

Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

Depth to bottom of fresh water 140'
Depth to bottom of usable water 1100' 1300' Base K

Surface pipe by Alternater 1 2 X
Surface pipe planned to be set 240'

Conductor pipe required
Projected Total Depth 4650' feet

Formation MISSISSIPPIAN

If OWWO: old well info as follows:

Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Western Kansas
Date 10/2/87 Signature of Operator or Agent Scott A. Oathead Title Geologist

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt.

This Authorization Expires 4-2-88 Approved By FH10-2-87

EFFECTIVE DATE: 10-2-87

Spud 10-6-87
Set 240

SE SW NE Sec. 7 Twp. 17S S. Rg. 27 East

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ ft. deep 2130' or formation with 50 feet of 60/40 Poz. w/6% Gel
2nd plug @ ft. deep 1150' or formation with 60 feet of 60/40 Poz. w/6% Gel
3rd plug @ ft. deep 260' or formation with 50 feet of 60/40 Poz. w/6% Gel
4th plug @ ft. deep 40' or formation with 10 feet of 60/40 Poz. w/6% Gel
5th plug @ ft. deep or formation with feet of

(2) Rathole to surface minus 5 feet 10BX

(b) Mousehole to surface minus 5 feet

PUSHER Bob Rowan
TD 4680 FORMATION MISS
SURFACE PIPE 8 5/8 @ 242
ANEHYDRITE 2126 ELEVATION
STARTING TIME & DATE 10-13-87 10:16 P.M.
COMPLETION TIME & DATE 7:08
1st PLUG @ 2130 FT. W/ 50 SX
2nd PLUG @ 1320 FT. W/ 80 SX
3rd PLUG @ 270 FT. W/ 40 SX
4th PLUG @ 40 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ SX
CEMENT COMPANY

TECHNICIAN Lacey
60/40 poz 6% gel
sent Dan
Filled
OCT 21 1987