

1 060790

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-21,267-00-00

C NW SW SE, SEC. 7, T 17 S, R 27 W78
990 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5422
Operator: Abercrombie Drilling, Inc.
Name & Address: 801 Union Center
Wichita, KS 67202

Lease Name Hanks Well # 1
County Lane 151.78
Well Total Depth 4670 Mississippi feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 301

Abandoned Oil Well Gas Well Input Well SWD Well O&A X

Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422
Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 1:00 pm Day: 2 Month: January Year: 19 86

Plugging proposal received from Tony Martin

(company name) Abercrombie Drilling (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2142' Elevation 2278'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at the base of the Cheyenne with 80 sx cement

3rd plug at 40' below the base of the surface pipe with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: 3:30 pm Day: 2 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 2172' with 50 sx cement, 2nd plug at 1500' with 80 sx
cement, 3rd plug at 341' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug
at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with
10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JAN 30 1986

CONSERVATION DIVISION

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE JAN 31 1986

INV. NO. 12200

1-2

FEB 5 1986

Signed Paul A. Luthi
(TECHNICIAN)

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: 12-20-85
month day year 2:45

API Number 15- 101-21,267-00-00
C. NW. SW. SE. Sec. 7, Twp. 17. S, Rge. 27. East West
(location)

OPERATOR: License # 5422
Name: Abercrombie Drilling, Inc.
Address: 801 Union Center
City/State/Zip: Wichita, KS 67202
Contact Person: Jack L. Partridge
Phone: 316-262-1841

990 Ft North from Southeast Corner of Section
2310 Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5422
Name: Abercrombie Drilling, Inc.
City/State: Wichita, KS

Nearest lease or unit boundary line 330 feet.
County Lane
Lease Name Hanks Well# 1
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

Well Drilled For: Well Class: Type Equipment:
 Oil Swd Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Depth to Bottom of fresh water 100 feet
Lowest usable water formation Dakota
Depth to Bottom of usable water 1150 feet
Surface pipe by Alternate: 1 2
Surface pipe to be set 300 feet
Conductor pipe if any required None feet
Ground surface elevation feet MSI
This Authorization Expires 6-17-86

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth
Projected Total Depth 4650 feet
Projected Formation at TD Miss.
Expected Producing Formations L/KC, Marm, Cher, Sand

Approved By: 12-17-85
Signature of Operator or Agent

Date 12-17-85 Signature of Operator or Agent

Jerry A. Langrehe

Exec. V.P. Abercrombie Drilling, Inc. Form G-1 4/84

More 18-20-85 set 300'

DTH

PUSHER Tony Martin

TD 4670' FORMATION Miss.

SURFACE PIPE 8 5/8" @ 301'

ANHYDRITE 2142' ELEVATION 2278'

STARTING TIME & DATE

COMPLETION TIME & DATE 3:30 PM, 1-2-86

1st PLUG @ 2172 FT. W/ 50 SX

2nd PLUG @ 1500 FT. W/ 80 SX

3rd PLUG @ 341 FT. W/ 50 SX

4th PLUG @ 40 FT. W/ 10 SX

RAT HOLE CIRCULATED W/ 10 SX

MOUSE HOLE CIRCULATED W/ SX

WATER WELL PLUGGED W/ SX

CEMENT COMPANY B.S. Titan

TECHNICIAN P. G.

1st base run by 50 2172
2nd Cheyenne 180 1500
3rd 40' out by 50 340
4th 400 SB 10
Cin 10 mat
60/40 w/ 6% gel

RECEIVED
STATE CORPORATION COMMISSION

JAN 30 1986

CONSERVATION DIVISION