

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-20719-00-00
Spot: NWSENE Sec/Twnshp/Rge: 13-17S-30W
670 feet from N Section Line, 640 feet from E Section Line
Lease/Unit Name: GRUSING F Well Number: 1
County: LANE Total Vertical Depth: 4641 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 SOUTH MAIN STE 200
WICHITA, KS 67202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 446 WITH 260 SX CMT
Production: Size 4.5 feet: 4640 WITH 150 SX CMT
Liner: Size feet: 8150.83

Well Type: OIL UIC Docket No: Date/Time to Plug: 09/04/2001 12:00 PM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Rcvd. from: GARY SHARP Company: TRANS PACIFIC Phone: (316) 262-3596

Proposed Plugging Method: CIBP @ 4150' & 2 SX CMT ON TOP. PERFORATE AT 1250' PUMP 80 SX CMT. PUMP 175 SX CMT DOWN ANNULUS. PRESSURE TEST.

Plugging Proposal Received By: STEVE DURRANT Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/04/2001 3:00 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 4597'. PERFS AT 4202-4509'. SET CIBP @ 4150' & DUMP 2 SX CMT ON TOP. FOUND FLUID LEVEL AT 2000'. PERFORATED AT 1250'. LOADED HOLE PUMPED IN FRESH WATER @ 4 BPM 600# STARTED CMT DOWN 4 1/2" PUMPED 145 SX CMT. MAXIMUM PRESSURE 600#. SHUT IN AT 300#. PUMPED DOWN 8 5/8" X 4 1/2" ANNULUS 175 SX CMT. MAXIMUM PRESSURE 250#. SHUT IN AT 200#.

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed

Kevin D. Strube

(TECHNICIAN)

RECEIVED

INVOICED

SEP 25 2001

DATE 9-25-01

SEP 12 2001

KCC WICHITA

NO. 2002060606

MP

FORM CR-2/3