

1090007

7-6

API NUMBER 15-101-21,518 -00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NW SE SW, SEC. 12, T 17 S, R 30 W/R

990 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4629

Lease Name Jennison Well # 1-12

Operator: Brito Oil Company, Inc.

County Lane 149.50

Name & Address 200 East First, Suite 208

Well Total Depth 4600 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 208

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Blue Goose Drilling Company License Number 5104

Address Box 1413, Great Bend, KS 67530

Company to plug at: Hour: 1 a.m. Day: 6 Month: 7 Year: 19 89

Plugging proposal received from Martin Miller

(company name) Blue Goose Drilling Company (phone) 316-264-0216

\_\_\_\_\_ Elevation 2846'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2236-64'

1st plug at 2270' with 50 sx cement, 2nd plug at 1385' with 80 sx cement,

3rd plug at 240' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

\_\_\_\_\_ Plugging Proposal Received by Michael R. Wilson  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 3:30 a.m. Day: 6 Month: 7 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 2270' with 50 sx cement,

2nd plug at 1385' with 80 sx cement,

3rd plug at 240' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

1989

07-07-89

CONSERVATION DIVISION  
WICHITA, KANSAS

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.

(if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 7-10-89

Signed Michael R. Wilson  
(TECHNICIAN)

FILE NO. 25284

7-6

NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date JUNE 20 1989 month day year  
NW SE SW Sec 12: Twp 17 S, Rg 30 X West

OPERATOR: License # 4629  
Name: Brito Oil Company, Inc.  
Address: 200 E. First, Suite 208  
City/State/Zip: Wichita, KS 67202  
Contact Person: Raul F. Brito  
Phone: 316-263-8787

990 feet from South line of Section  
3630 feet from East line of Section  
(Note: Locate well on Section Plat Below)

CONTRACTOR: License #: 5104  
Name: Blue Goose Drilling Co.

County: Lane  
Lease Name: Jennison Well #: 1-12  
Field Name: WC  
Is this a Prorated Field? yes X no  
Target Formation(s): Mississippi  
Nearest lease or unit boundary: 990'  
Ground Surface Elevation: 2839 EGL feet MSL  
Domestic well within 330 feet: yes X no  
Municipal well within one mile: yes X no  
Depth to bottom of fresh water: 175'  
Depth to bottom of usable water: 1290' 1300'  
Surface Pipe by Alternate: 1 X 2  
Length of Surface Pipe Planned to be set: 200'  
Length of Conductor pipe required: None  
Projected Total Depth: 4600'  
Formation at Total Depth: Mississippi  
Water Source for Drilling Operations:  
well farm pond X other

Well Drilled For: Well Class: Type Equipment:  
X Oil Inj Infield X Mud Rotary  
Gas Storage Pool Ext. Air Rotary  
OAWO Disposal X Wildcat Cable  
Seismic; # of Holes

If OAWO: old well information as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_  
Comp. Date: \_\_\_\_\_ Old Total Depth \_\_\_\_\_

Directional, Deviated or Horizontal wellbore? yes X no  
If yes, total depth location: \_\_\_\_\_


DWR Permit #: \_\_\_\_\_  
Will Cores Be Taken?: yes X no  
If yes, proposed zone: \_\_\_\_\_  
200' Alt. II Req.

Spud 6-28-89

AFFIDAVIT

PUSHER Martin Miller  
TD 4600 FORMATION Mussel  
SURFACE PIPE 8 5/8 @ 208'  
ANHYDRITE 2 3/4 @ 284' ELEVATION 2846  
STARTING TIME & DATE 1:00 AM 7-6-89  
COMPLETION TIME & DATE 3:30 AM 7-6-89  
1st PLUG @ 2270 FT. W/ 50 SX  
2nd PLUG @ 1385 FT. W/ 80 SX  
3rd PLUG @ 240 FT. W/ 40 SX  
4th PLUG @ 40 FT. W/ 10 SX  
RAT HOLE CIRCULATED W/ 15 SX  
MOUSE HOLE CIRCULATED W/ \_\_\_\_\_ SX  
WATER WELL PLUGGED W/ cement completely  
CEMENT COMPANY B. J. Jutan  
TECHNICIAN Mike Wilson

RECEIVED  
STATE CORPORATION COMMISSION  
JUL - 7 1989  
92-5633  
12 17 30W  
12 17 30W  
Agent: Kansas



- REMEMBER TO:
- File Drill Pit Application (form COP-1) with Intent to Drill;
  - File Completion Form ACO-1 within 120 days of spud date;
  - File acreage attribution plat according to field proration orders;
  - Notify appropriate district office 48 hours prior to workover or re-entry;
  - Submit plugging report (CP-4) after plugging is completed;
  - Obtain written approval before disposing or injecting salt water.