

7-11

070696

To: # 1  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- NA 15-101-21455-00-01  
N/2 NE, SEC. 12, T 17 S, R 30 W/R

TECHNICIAN'S PLUGGING REPORT

4620 feet from S section line  
1320 feet from E section line

Operator License # 6113

Lease Name York Well # 1

Operator: Landmark Oil Exploration, Inc.  
Name & Address: 250 North Water, Suite 308  
Wichita, KS 67202

County Lane 149.70

Well Total Depth 4606 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 325

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Landmark Oil Exploration, Inc. License Number 6113

Address 250 North Water, Suite 308, Wichita, KS 67202

Company to plug at: Hour: 6:15 p.m. Day: 11 Month: 7 Year: 19 89

Plugging proposal received from Russell Bright

(company name) Landmark Oil Exploration, Inc. (phone) 316-265-8181

were: 4 1/2" at 4605' PBTD 4514' Perfs at 4452-57'

1st plug sand back to 4400' and dump 4 sx cement on top of sand through bailer,

2nd plug shoot casing at 1750', pump through casing 50 sx cement at 1700',

3rd plug pump 70 sx cement at 1100', 4th plug pump 40 sx cement at 345',

5th plug pump 15 sx cement at 40'.

Plugging Proposal Received by Glenn R. Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 8:30 p.m. Day: 11 Month: 7 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4400' and dumped 4 sx cement on top of sand through bailer,

2nd plug shot casing at 1750', pumped through casing 50 sx cement,

3rd plug pumped 70 sx cement at 1100',

4th plug pumped 40 sx cement at 345',

5th plug pumped 15 sx cement at 40'.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1750' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED (400) observe this plugging.

DATE 7-20-89

Signed Dan Jordan (TECHNICIAN)

INV. NO. 25374 7-11

RECEIVED  
STATE CORPORATION COMMISSION  
7-17-89  
CONSERVATION DIVISION  
Wichita, Kansas