

1060334

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,039 -00-00

W/2 W/2 NB SEC. 10 ; T 17 S, R 30 W/R
4110 feet from N SE Corner of
2310 feet from W SE Corner of
XXX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181 & 5238

Lease Name Steward 'K' Well # 2

Operator: Donald C. Slawson & Petroleum, Inc
Name & Address: 200 Douglas Building
Wichita, KS 67202

County Lane

Well Total Depth 4604 149.63 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 472

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Slawson Drilling Co., Inc. License Number 5657

Address 200 Douglas Building, Broadway & Douglas, Wichita, KS 67202

Company to plug at: Hour: 2:00 pm Day: 14 Month: September Year: 19 84

Plugging proposal received from Jim Loftis

(company name) Slawson (phone) 316-263-3201

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2200' with 50 sx cement

2nd plug at 1400' with 50 sx cement

3rd plug at 520' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 4:30 pm Day: 14 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2200' with 50 sx cement, 2nd plug at 1400' with

50 sx cement, 3rd plug at 520' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 24 1984

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton
(If additional description is necessary, use BACK of this form.)

INVOICED

(xxx / did not) observe this plugging.

DATE 10-2-84

Signed Paul A. Luthi (TECHNICIAN)

INV. NO. 3984

9-12