

To: 1070113  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,974-100-01

NE NW NE, SEC. 10, T 17 S, R 30 W/R  
4950 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039

Lease Name Stewart Well # 1

Operator: L. D. Davis  
Name & Address: R. R. 1, Box 183 B  
Great Bend, KS 67530

County Lane 151.45

Well Total Depth 4660' feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 442

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor L. D. Davis License Number 6039

Address R. R. 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: 2:30 pm Day: 27 Month: December Year: 19 85

Plugging proposal received from Greg Downing

(company name) L. D. Davis (phone) 316-564-3646

were: 4 1/2" at 4656' PBD 4633' Perfs at 4514-17'

2-staged from 1350' to surface

Squeeze well with 1 sack hulls, 25 sx cement, 18 sx gel, release 8 5/8" rubber plug and pump 110 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:00 pm Day: 27 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 2-staged from 1350' to surface. Squeezed well with 1 sack hulls, 25 sx cement, 18 sx gel, released 8 5/8" rubber plug and pumped 110 sx cement.

Maximum pressure 225 psi and shut in vac.

Remarks: No.recovery. Used 60/40 Pozmix 6% gel by Halliburton.  
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE JAN 06 1986

Signed Dan Goodrow (TECHNICIAN)

INV. NO. 11839  
12-27

JAN 2 1986