

To: 1 071069  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

5-19

API NUMBER 15-101-21,369-00-00 135

SE SE SW, SEC. 9, T. 17 S, R. 30 W/E

330 feet from S section line

2970 feet from E section line

Lease Name Schadel Well # 1

County Lane 148.85

Well Total Depth 4580 feet

Conductor Pipe: Size        feet

Surface Casing: Size 8 5/8 feet 464

TECHNICIAN'S PLUGGING REPORT

Operator License # 30748

Operator: Image Petroleum Company

Name:       

Address Box 554

Ness City, KS 67560

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated       

Plugging Contractor Image Petroleum Company License Number 30748

Address P.O. Box 554, Ness City, KS 67560

Company to plug at: Hour: 2 p.m. Day: 19 Month: 5 Year: 19 92

Plugging proposal received from Max Parsons

(company name) Image Petroleum Company (phone) 913-798-2725

were: 4 1/2" at 4579' w/250 sx cement, PBD 4250', Perfs at 4156-86', 2-staged 2240-0' w/500 sx cement

1st plug pump 600 lbs. hulls ahead of 200 sx cement down 4 1/2".

Check backside.

Plugging Proposal Received by Dan Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 3:30 p.m. Day: 19 Month: 5 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug pumped 600 lbs. hulls ahead of 200 sx cement down 4 1/2".

Maximum pressure 1200 psi and shut in 0 psi.

Backside would not take at 1000#.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 27 1992

Remarks: Used 60/40 Pozmix 8% gel by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form.)

I did  did not observe this plugging.

DATE 6-3-92

INV. NO. 35365

Signed Dan Goodrow  
(TECHNICIAN)