

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-21822-00-00
Spot: E2E2W2 Sec/Twnshp/Rge: 6-17S-30W
2640 feet from N Section Line, 2220 feet from W Section Line
Lease/Unit Name: B BROOKS Well Number: 1
County: LANE Total Vertical Depth: 4615 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: BOX 783188 8100 E 22ND ST. N. #700
WICHITA, KS 67278

Surface Casing Size: 8.625 feet: 266

\$ 149.09

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/20/2003 1:00 PM
Plug Co. License No.: 6039 Plug Co. Name: L.D. DRILLING, INC.
Proposal Rcvd. from: DORAN MARGHEIM Company: L.D. DRILLING, INC. Phone: (620) 793-3051

Proposed Plugging Method: 1ST PLUG AT 2320' WITH 50 SX CMT. 2ND PLUG AT 1360' WITH 80 SX CMT. 3RD PLUG AT 660' WITH 50 SX CMT. 4TH PLUG AT 290' WITH 50 SX CMT. 5TH PLUG WIPER PLUG TO 40'. 40-0' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: RICHARD LACEY WitnessType: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 10/20/2003 4:15 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:
1ST PLUG AT 2320' WITH 50 SX CMT. 2ND PLUG AT 1360' WITH 80 SX CMT. 3RD PLUG AT 660' WITH 50 SX CMT. 4TH PLUG AT 290' WITH 50 SX CMT. 5TH PLUG WIPER PLUG TO 40'. 40-0' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE.

RECEIVED
OCT 28 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

RECEIVED
OCT 21 2003
KCC Dodge City

Signed Richard W. Lacey
(TECHNICIAN)

INVOICE
DATE 10-28-03
NO. 2004060691

Form CP-33