

State Geological Survey
WICHITA BRANCH

AFFIDAVIT OF COMPLETION FORM

ACO-1 WELL HISTORY

Compt. _____

TYPE

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

(F) Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

(C) Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 8640 EXPIRATION DATE 6-30-84

OPERATOR Weilert Oil Company Inc. API NO. 15-135-22405-00-08

ADDRESS 2604 E. General Rd. COUNTY Ness

Hays, Ks. 67601 FIELD Wildcat

** CONTACT PERSON Michael D. Weilert PROD. FORMATION Mississippi

PHONE (913) 625-2888

PURCHASER Clear Creek Inc. LEASE Horacek

ADDRESS 818 Century Plaza Bldg. WELL NO. 1

Wichita, KS 67202 WELL LOCATION NW NW NE

DRILLING CONTRACTOR Helberg Oil Company 330 Ft. from North Line and

ADDRESS Box 32 2310 Ft. from East Line of (E)

Morland, Ks. 67650 the NE (Qtr.) SEC 35 TWP 16 RGE 25 (W).

PLUGGING CONTRACTOR _____ WELL PLAT _____ (Office Use Only)

ADDRESS _____ KCC _____

KGS

SWD/REP _____
PLG. _____

TOTAL DEPTH 4510 PBTD _____

SPUD DATE 6-15-1983 DATE COMPLETED July 6, 1983

ELEV: GR 2517 DF _____ KB 2522

DRILLED WITH (~~CABLE~~) (ROTARY) (~~XXX~~) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE _____

Amount of surface pipe set and cemented 213' DV Tool Used? _____

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO. Other _____

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

RELEASED
Date: AUG 1 1984
FROM CONFIDENTIAL

RECEIVED
STATE CORPORATION COMMISSION
APR 21 1989
CONSERVATION DIVISION
Wichita, Kansas

Michael D. Weilert AFFIDAVIT

that: _____, being of lawful age, hereby certifies

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

Weilert Oil Company, Inc.
(Name)

SIDE TWO

15-135-22405-00-00

ACO-1 WELL HISTORY

OPERATOR Weilert Oil Company Inc. LEASE Horacek SEC.35 TWP.16 RGE.25

FILL IN WELL INFORMATION AS REQUIRED: WELL NO. 1

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Check if no Drill Stem Tests Run.				
Sand & Shale	0	40		
Sand & Shale	40	225		
Shale	225	605		
Shale	605	1282		
Shale	1282	1834		
Sand & Shale	1834	1876		
Anhydrite	1876	1944		
Shale	1876	2150		
Sand & Shale	2150	2448		
Shale	2448	2649		
Shale	2649	2825		
Shale	2825	2960		
Shale	2960	3115		
Shale & Lime	3155	3245		
Shale & Lime	3245	3382		
Shale & Lime	3382	3509		
Shale	3509	3644		
Shale & Lime	3644	3791		
Shale & Lime	3791	3908		
Shale & Lime	3908	3986		
Shale & Lime	3986	4083		
Lime	4083	4153		
Lime	4153	4212		
Lime	4212	4282		
Lime	4282	4335		
Lime	4335	4379		
Lime	4379	4420		
Lime	4420	4449		
Lime	4449	4510		
T.D.	4510			
Run Casing				

If additional space is needed use Page 2, Side 2

Report of all strings set— surface, intermediate, production, etc. CASING RECORD (New) ~~xxx (Used)~~

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/2"	8 5/8"	20#	213'	Common	130	3% Cal Cl 2% Gel
Production String Bottom Stage	7 7/8"	5 1/2"	15.5#	4509'	Common	165	10% salt
Production String Top Stage					Common	425	50/50 Poz 6% Gel

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD					
Size	Setting depth	Packer set at			
2 7/8"	4501.89		4	SSB's	4392-98
			4	SSB's	4389-91

RECEIVED
STATE CORPORATION COMMISSION
APR 21 1989
CONSERVATION DIVISION
Wichita, Kansas

ACO-1 WELL HISTORY

PAGE TWO (Page Two)

OPERATOR Weilert Oil Company, Inc LEASE NAME Horacek #1 SEC. 35 TWP. 16 RGE. 25W

FILL IN WELL LOG AS REQUIRED:

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

State Geological Survey
WICHITA BRANCH

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DRILL STEM TESTS:				
D.S.T. #1-----Fort Scott-----	4385	4420	Heebner	3847
RECOVERY: 510' Total Fluid			Lansing-K.C.	3903
140' Heavy mud cut. gassy oil			Base K.C.	4185
370' Slightly mudcut very gassy oil			Fort Scott	4390
1400' Gas in pipe			Mississippi	4489
Tool Open-----30 minutes	I.F.P.-----	69-131-----	P.S.I.	
Tool closed-----30 minutes	F.F.P.-----	155-214-----	P.S.I.	
	S.I.P.-----	405-----	P.S.I.	
Second Open & Closed	S.I.P.-----	381-----	P.S.I.	
Tool Open-----60 minutes				
Tool Closed-----30 minutes				
D.S.T. #2-----Mississippi-----	4475	4510		
RECOVERY: 120' Total Fluid				
60' heavy oil cut mud				
60' oil cut mud				
100' Gas in pipe				
Tool Open-----30 minutes	I.F.P.-----	59-67-----	P.S.I.	
Tool closed-----30 minutes	F.F.P.-----	67-71-----	P.S.I.	
	S.I.P.-----	1136-----	P.S.I.	
Second Open and closed	S.I.P.-----	1049-----	P.S.I.	
Tool Open-----60 minutes				
Tool Closed-----30 minutes				

RECEIVED
 STATE CORPORATION COMMISSION
 APR 21 1989
 CONSERVATION DIVISION
 WICMB, Kansas

Amount and kind of material used		Depth interval treated
250 Gallons	15% INS	4489-91
8000 Gallons	15% INS	4392-98
Date of first production 7-15-83	Producing method (flowing, pumping, gas lift, etc.) Pumping	Gravity 36
Estimated Production -I.P.	Oil 7 bbls.	Gas MCF 85 % 50 bbls.
Disposition of gas (vented, used on lease or sold)		Perforations