



15-101-20012 -00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUL 13 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Herb Hason of Dunne-Gardner Petr., Inc., has this date requested permission to plug the following described well:

Mr. Hason guarantees payment of the plugging fee.

Operator's full Name: Thunder Bird Drilling Co. Petroleum Resources,

Complete Address: Box #18407, Wichita, Kansas.

Lease Name: Hagans Well No. H-1

Location: NW-NE-NE Sec. 2 Twp. 17 Rge. (E)(W) 27

County: Lane Total Depth 4580' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Hason was instructed to plug the well as follows:

320'--8 5/8" Surface casing, cement circulated with 225 Sx.  
Top of Dakota section @ 775'.

Circulate hole with heavy mud. Pull DP to 1000' and displace 100 Sx.  
cement thru DP. Pull DP to 340' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 3 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

Conservation Division Agent