



15-101-20009-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 7 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Herb Mason of Dunne-Gardner Petroleum, Inc has this date requested permission to plug the following described well:

Mr. Mason guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drilling and Petroleum Resources,

Complete Address: Box #18407, Wichita, Kansas.

Lease Name: Hagans Well No. A-1

Location: NE-NE-SE Sec. 1 Twp. 17 Rge. (E)(W) 27

County: Lane Total Depth 4545' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Mason was instructed to plug the well as follows:

281'--8 5/8" Surface casing, cement circulated with 225 Sx.  
Top of Dakota section @ 500'.

Circulate hole with heavy mud. Pull DP to 720' and displace 100 Sx.  
cement thru DP. Pull DP to 270' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

M. L. Nichols  
Conservation Division Agent