



15-101-20037-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 30 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Eddie Abercrombie of Rains-Williamson Oil Co. Inc., has this date requested permission to plug the following described well:

Mr. Abercrombie guarantees payment of the plugging fee.

Operator's full Name: Patrick Petroleum Corporation,

Complete Address: Suite 330, Page Court, Wichita, Kansas.

Lease Name: Schnieg Estate Well No. 1

Location: CNW-NW Sec. 6 Twp. 17 Rge. (E)(W) 27

County: Lane Total Depth 4665' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Abercrombie was instructed to plug the well as follows:

285'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 700'.

Circulate hole with heavy mud. Pull DP to 925' and displace 110 Cu. Ft. cement thru DP. Pull DP to 310' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent