



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Bob Delaney of Rains & Williamson Oil Co., has this  
date requested permission to plug the following described well:

Mr. Delaney guarantees payment of the plugging fee.

Operator's full Name: Hull Drilling Company,

Complete Address: 415 Page Court, Wichita, Kansas.

Lease Name: Hineman Well No. 1

Location: CSW-NE Sec. 33 Twp. 18 Rge. (E)(W) 28

County: Lane Total Depth 4635' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Delaney was instructed to plug the well as follows:

247'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section ~ 700'.

Circulate hole with heavy mud. Pull DP to 925' and displace 110 Cu. Ft.  
cement thru DP. Pull DP to 280' and displace 30 Cu. Ft. cement thru DP.  
Pull DP, set bridge 40' with 3 sack bolls and 10 Cu. Ft. cement to  
bottom of cellar.

Very truly yours,

H. L. Nichols  
Conservation Division Agent