



15-101-20108-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 16 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Claude Norwood of DNB Drilling, Incorporated has this date requested permission to plug the following described well:

Mr. Norwood guarantees payment of the plugging fee.

Operator's full Name: DNB Drilling, Incorporated,

Complete Address: 701 First National Bank Building, Wichita, Kansas.

Lease Name: Ware Well No. 1

Location: CNW-NE Sec. 30 Twp. 18 Rge. (E)(W) 28

County: Lane Total Depth 4610' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Norwood was instructed to plug the well as follows:

308'--8 5/8" Surface casing, cement circulated with 200 Sx.

Circulate hole with heavy mud. Pull DP to 850' and displace 70 Sx.

cement thru DP. Pull DP to 310' and displace 20 Sx. cement thru DP.

Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to

bottom of cellar.

Very truly yours,

Leo F. Massey  
Conservation Division Agent