

State of Kansas



15-101-20132-00-80

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION

DEC 11 1974

CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Don Favinger of Abercrombie Drilling, Inc., has this
date requested permission to plug the following described well:Mr. Favinger guarantees payment of the plugging fee.Operator's full Name: A. L. Abercrombie, Incorporated,Complete Address: 801 Union Center, Wichita, Kansas.Lease Name: Seifried Well No. 2Location: CN/2-NW-NW Sec. 25 Twp. 18 Rge. (E)(W) 28County: Lane Total Depth 4270' Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Favinger was instructed to plug the well as follows:287'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 625'.Circulate hole with heavy mud. Pull DP to 850' and displace 110 Cu. Ft.
cement thru DP. Pull DP to 310' and displace 30 Cu. Ft. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to
bottom of cellar.

Very truly yours,

 Conservation Division Agent