



15-101-20116-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 22 1974
CONSERVATION DIVISION
WICHITA, KANSAS

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Engle of Slawson Drlg. has this
date requested permission to plug the following described well:

Mr. Engle guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson

Complete Address: 408 120 Bldg., Wichita, Ks.

Lease Name: Selfridge "T" Well No. 1

Location: NW NW SW Sec. 12 Twp. 18 Rge. (E)(W) 28

County: Lane Total Depth 4641' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Engle was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 950' and displace

70 sk com thru drill pipe. Heavy mud to 240' & displace 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls

and 10 sk cmt to base of cellar.

Very truly yours,

Conservation Division Agent