



15-101-20020-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 13 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Albert Freeman of Sage Drilling Company, Inc., has this date requested permission to plug the following described well:

Mr. Freeman guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drilling, Inc., c/o Petroleum Resources,

Complete Address: Box #18407, Wichita, Kansas.

Lease Name: Fink Well No. 1

Location: NW-SW-NW Sec. 24 Twp. 16 Rge. (E)(W) 27

County: Lane Total Depth 4696' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Freeman was instructed to plug the well as follows:

283'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 800'.

Circulate hole with heavy mud. Pull DP to 1025' and displace 100 Sx.
cement thru DP. Pull DP to 310' and displace 25 Sx. cement thru DP.
Pull DP and set bridge @ 40' with 1/2 sack hulls then 10 Sx. cement to
bottom of cellar.

Very truly yours,

A. G. J. Jickels
Conservation Division Agent