



15-101-20021-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 28 1973

CONSERVATION DIVISION
WICHITA, KANSAS

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Darrell Kelso of Kelso Casing Pulling has this

date requested permission to plug the following described well:

Mr. Kelso guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drilling Company,

Complete Address: Box #18407, Wichita, Kansas.

Lease Name: Fink Well No. C-1.

Location: SW-NE-NE Sec. 24 Twp. 16 Rge. (E)(W) 27

County: Lane Total Depth 4567 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Kelso was instructed to plug the well as follows:

296'--8 5/8" Surface casing, cement circulated with---
4557'--5 3/4" Production casing cemented on bottom with 250 Sx. No plug
back indicated. Top of perforations ? 4035'.

Push plug to 4000', sand back from 4000' to 3975' and set 5 Sx. cement
with dump bailer. Pull 5 3/4" casing and squeeze well with 5 sacks hulls,
30 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

H. L. [Signature]
Conservation Division Agent