



15-101-20048-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 13 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bob Delaney of Rains & Williamson Oil Co., has this date requested permission to plug the following described well:

Mr. Delaney guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Oil Company, Incorporated,

Complete Address: 435 Page Court, 220 West Douglas, Wichita, Kansas.

Lease Name: Bentley Well No. 1

Location: SE-SE-NW Sec. 17 Twp. 16 Rge. (E)(W) 27

County: Lane Total Depth 4650' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Delaney was instructed to plug the well as follows:

311'--8 5/8" Surface casing, cement circulated with 190 Sx.
Top of Dakota section @ 775'.

Circulate hole with heavy mud. Pull DP to 1000' and displace 110 Cu. Ft. cement thru DP. Pull DP to 310' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 20' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

H. L. Nichols
Conservation Division Agent