

State of Kansas



15-101-30003-00-00

FORM - CP-2
Rev. 9-8-64

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
PAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 19 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Cal Roberts of Leben Drilling, Inc., has this

date requested permission to plug the following described well:
Sioux Petroleum,

Mr. Roberts guarantees payment of the plugging fee.

Operator's full Name: Sioux Petroleum,

Complete Address: Dighton, Kansas.

Lease Name: Broughton Well No. 2

Location: CNW-NE Sec. 15 Twp. 16 Rge. (E) (W) 27

County Lane Total Depth 4506 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Roberts was instructed to plug the well as follows:

106' -- 8 5/8" Surface pipe, cement circulated with 125 Sx.

Circulate hole with heavy mud, set plug @ 540' and 20 Sx. cement.

"	"	120' with $\frac{1}{2}$ sk. hulls &
		20 Sx. cement.
"	"	40' with $\frac{1}{2}$ sk. hulls &
		10 Sx. cement.

Very truly yours,

Conservation Division Agent