

State of Kansas



FORM - CP-2  
Rev. 9-8-64

15-101-30004-00-00

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

## State Corporation Commission

### CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

#### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

AUG 10 1965

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Claude Norwood of Leben Drilling, Inc. has this

date requested permission to plug the following described well:  
Sioux Petroleum,

Mr. Norwood guarantees payment of the plugging fee.

Operator's full Name: Sioux Petroleum,

Complete Address: Dighton, Kansas.

Lease Name: Broughton Well No. 3

Location: NBSW  
CSW NE 00K66 Sec. 15 Twp. 16 Rge. (E)(W) 27

County Lane Total Depth 4185 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Norwood was instructed to plug the well as follows:

106'--8 5/8" Surface pipe, cement circulated with 125 Sx.

Circulate hole with heavy mud, set plug @ 600' and 15 Sx. cement.

"	"	120'	with $\frac{1}{2}$ sk. hulls &
			15 Sx. cement.
"	"	40'	with $\frac{1}{2}$ sk. hulls &
			10 Sx. cement.

Very truly yours,

M. L. Dechule  
Conservation Division Agent