

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-217150000

LEASE NAME BURMEISTER

WELL NUMBER 1-27

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

960 Ft. from S/W Line of Section (circle one)

1600 Ft. from E/W Line of Section (circle one)

50' E & 30' S of

LEASE OPERATOR LANDMARK ENERGY EXPL., INC./Vess Oil Corp.

SPOT LOCATION NE SW SE

ADDRESS 1861 N. Rock Rd., Suite 205

SEC. 27 TWP. 18S S. RGE 28 W or

CITY, STATE, ZIP Wichita, Kansas 67206

COUNTY LANE

PHONE# (316) 683-8080 OPERATORS LICENSE NO. 06113

Date Well Completed 3-10-96

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Plugging Commenced 3-10-96

Date Plugging Completed 3-10-96

The plugging proposal was approved on March 9, 1996

by Gary Winters

(KCC District Agent's Name)

Is ACO-1 filed? by operator if not, is well log attached?

Producing Formation(s) Depth to Top Bottom T.D. 4620'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
surface		0	335'	8 5/8"	335'	none

Described in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

50 sx. @ 2110', 80sx. @ 1380', 40 sx. @ 700', 40 sx. @ 360', 10 sx. @ 40', 15 sx. in rat hole

Total: 235 sx. 60/40 Pozmix, 1/4# flo seal per sk. Allied cementing

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor L. D. DRILLING, INC.

License No. 6039

Address R.R. 1 Box 183 B Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Landmark Energy Expl., Inc./Vess Oil Corporation

STATE OF KANSAS COUNTY OF BARTON, ss.

Bessie DeWerff (Employee of Operator or (Operator) of above-described well, being

only sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Bessie DeWerff


(Address) R.R. 1 Box 183 B Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 13th day of March, 19 96

Rashell Patten

Notary Public
Rashell Patten

My Commission Expires: 2-2-99



Form CP-
Revised