

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 COLORADO DERRY BUILDING
 WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15 - 101 - 20,667-0000

LEASE NAME Seifried

TYPE OR PRINT
 PLEASE FILL OUT COMPLETELY
 AND MAKE REQUIRED AFFIDAVIT.

WELL NUMBER 1 (one)

SPOT LOCATION SE SW SW

LEASE OPERATOR Moble C. Hoover

SEC. 25 TWP. 18 (E) OR (W)

ADDRESS NBC Building Suite 302 El Dorado, Arkansas 71730

COUNTY Lane

PHONE #(501) 863-4531 OPERATORS LICENSE NO. 5408

DATE WELL COMPLETED 7/14/82

CHARACTER OF WELL Oil
 (OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

PLUGGING COMMENCED 7/1/85 10:10 AM

PLUGGING COMPLETED 7/1/85 10:45 AM

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Wichita, Kansas & Dodge City, Kansas

IS ACG-1 FILED? Yes IF NOT, IS WELL LOG ATTACHED? _____

PRODUCING FORMATION Kansas City DEPTH TO TOP 4018' KB BOTTOM 4028' KB T.D. 4204' PBTD

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS | CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Kansas City	oil	4018	4028	8 5/8"	285'	None
				4 1/2"	4261'	None

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. Pumped down 4 1/2" casing as follows: 50 sacks of 50-50 Pozmix, 2% gel, 2% CaCl, 1/2# Celloflake per sack, followed with approximately 3000 gals. of fresh water, then 120 sacks of 50-50 Pozmix, 2% gel, 3% CaCl. Maximum pressure 2500#. Shut in pressure 500#. Note perforations 4022-4028' KB & 700-703' KB, four shots per foot.

Note: Checked well 7/2/85; top of cement 15' from surface.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Edw. C. Myers Jr. LICENSE NO. 3961 KS Engr.

ADDRESS Rt. 1 Box 323 Great Bend, Kansas 67530 Phone 316-792-2068

RECEIVED
 STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Barton SS.

III 08 1985

Edw. C. Myers Jr.

(EMPLOYEE OF OPERATOR) OR
 CONSERVATION DIVISION
 Wichita, Kansas

(OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) Edw. C. Myers Jr.
 (ADDRESS) Rt 1 Box 323 Gr Bend



SUBSCRIBED AND SWORN TO BEFORE ME THIS 5 DAY OF July, 1985

Cheryl Merrell
 NOTARY PUBLIC

MY COMMISSION EXPIRES: 1-27-86