

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-101-21,679-00-00

LEASE NAME Albin

WELL NUMBER 1

330 Ft. from S Section Line

330 Ft. from <sup>W</sup> Section Line

SEC. 17 TWP. 16 RGE. 27 (E) or (W)

COUNTY Lane

Date Well Completed 9-26-94

Plugging Commenced 9-26-94

Plugging Completed 9-26-94

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Staab Oil Co.

ADDRESS 1960 280th Avenue, Hays, KS. 67601

PHONE#(913) 625-3013 OPERATORS LICENSE NO. 6037

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-26-94 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? No If not, Is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4,588'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	239'	Cmtd. w/165 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet each set.

Spot 50 sax cement @2,150' thru drill pipe. Push bridge plug to 1,350', spot 80 sax cement on plug thru drill pipe. Push bridge plug to 650', spot 40 sax cement on plug thru drill pipe. Push plug to 270', spot 40 sax cement on plug thru drill pipe. Push bridge plug to 40'. dump 10 sax on plug. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co. License No. 160

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Staab Oil Co.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman Contractor (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack P. Beeman, Sec. - Treas.

(Address) Shields Bldg., Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 4th day of October

Ruth Phillips  
Notary Public

My Commission Expires:



RECEIVED  
STATE CORPORATION COMMISSION  
OCT 06 1994



Shields


Russell, Kansas

WELL LOG

15-10-21679-00-00

Operator: Staab Oil Company  
 Well: Albin #1  
 Commenced: September 16, 1994  
 Completed: September 26, 1994  
 Contractor: Shields Drilling Co.

Well Description: SW SW SW  
 Sec. 17-16S-27W  
 Lane County, KS.



Elevation: 2,717' KB  
 Treatment:  
 Production: D & A  
 Tops:

CASING RECORD

Size	Run	Pulled
8 5/8"	239'	Cmtd. w/165 sax

..... Figures Indicate Bottom of Formations .....

Sand	2,122'	
Anhydrite	2,158'	
Shale	2,895'	
Shale & lime	3,998'	
Lime	4,588'	RTD

RECEIVED  
STATE CORPORATION COMMISSION

OCT 06 1994

WICHITA KANSAS

Notes