


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-101-30004-0000 Form CP-4

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Lane _____ County. Sec. 15 Twp. 16S Rge. 27W (E) _____ (W) _____
Location as "NE/CNW/SW" or footage from lines _____ C NE SW _____
Lease Owner Sioux Petroleum Co.
Lease Name Broughton Well No. 3
Office Address 38 Robertson Road, Pueblo, Colo.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 8-7-65 19_____
Application for plugging filed 8-7-65 19_____
Application for plugging approved 8-7-65 19_____
Plugging commenced 8-7-65 19_____
Plugging completed 8-7-65 19_____
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19_____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Moreland, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4185 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	107'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set plug @ 600' with 15 sacks cement
Set plug @ 120' with 15 sacks cement & 1/3 sack hulls
Set plug @ 40' bridged with 1/2 sk. hulls to hold weight of kelly
10 sks cement

STATE CORPORATION COMMISSION

AUG 20 1965

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address Box 486, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Leslie Kite

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

P. O. Box 486, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of August, 19 65

My commission expires April 1, 1967

Ulauda Nichols
Notary Public.

15-101-30004-00-00

DRILLER'S LOG

COMPANY: Sioux Petroleum Co.
CONTRACTOR: LEBEN DRILLING, INC.
FARM: BROUGHTON #3
LOCATION: C NE SW Sec. 15-16S-27W
LANE COUNTY, KANSAS
COMMENCED: 7-31-65
COMPLETED: 8-7-65

0	536	Shale
536	2032	Shale & Sand
2032	2059	Shale
2059	2096	Anhydrite
2096	2680	Shale & Shells
2680	3812	Shale & Lime
3812	4185	Lime
	<u>4185</u>	<u>RTD - D. & A.</u>

Set 8 5/8" used surface casing @ 107' with 125 sacks 60-40
Posmix Sunset 2% Gel

I, Leslie Kite, do hereby certify that the above and fore-
going is a true and correct copy of the log of the Broughton
#3 well, located C NE SW Sec. 15-16 South-27 West, of Lane
County, Kansas, as reflected by the records of Leben Drilling,
Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS)
COUNTY OF BARTON) SS

Subscribed and sworn to before me, a Notary Public,
in and for Barton County, Kansas, this 9th day of August, 1965.

Ulanda Nichols

Ulanda Nichols

My Commission Expires:
April 1, 1967

STATE COMMISSIONER OF REVENUE
AUG 10 1965
CONSERVATION DIVISION
WICHITA, KANSAS