


15-101-20425-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

LANE _____ County. Sec. 15 Twp. 16 Rge. 27W (E) _____ (W) _____
Location as "NE/CNW/SW" or footage from lines 100' E of NW NE NE
Lease Owner DONALD C. SLAWSON
Lease Name BROUGHTON 'G' Well No. 2
Office Address 200 Douglas Building Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 15, 19 80
Application for plugging filed December 15, 19 80
Application for plugging approved December 15, 19 80
Plugging commenced December 15, 19 80
Plugging completed December 15, 19 80
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4530 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	333.28'	surface	342'	8 5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st plug @ 1500' w/70 sx
2nd plug @ 330' w/35 sx
Bridge @ 40' w/10 sx
5 sx in Rat Hole

RECEIVED
JAN 3 1980
STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor SLAWSON DRILLING CO., INC.
Address 200 Douglas Building Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
James C. Remsberg (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James C. Remsberg
JAMES C. REMSBERG
200 Douglas Building Wichita, Kansas 67202 (Address)

SUBSCRIBED AND SWORN TO before me this 24th day of January 19 80

My commission expires 6/12/82
SHERRY L. KENDALL
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Appt. Exp. 6/12/82

SHERRY L. KENDALL
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Appt. Exp. 6/12/82

Sherry L. Kendall
Notary Public.

WELL LOG

15-101-20425-00-00

OPERATOR: **DONALD C. SLAWSON**
 200 DOUGLAS BUILDING
 WICHITA, KANSAS 67202

LEASE: #2 Broughton 'G'
 100' E/NW NE NE Sec. 15-16-27W
 Lane County, Kansas

CONTRACTOR: **SLAWSON DRILLING COMPANY, INC.**
 200 DOUGLAS BUILDING
 WICHITA, KANSAS 67202

COMMENCED: December 3, 1980 ⁷⁹ JDKCC

COMPLETED: December 15, 1980 ⁷⁹

CASING: Surface - 8 5/8" @ 342' w/250 sx 60/40 poz

- 0 - 344 Surface hole
- 344 - 1182 Shale and sand
- 1182 - 1960 Shale and shales
- 1960 - 1988 Shale
- 1988 - 2041 Anhydrite
- 2041 - 2544 Shale
- 2544 - 3652 Lime and shale
- 3652 - 3915 Lime
- 3915 - 3958 Lime and shale
- 3958 - 4161 Lime
- 4161 - 4217 Lime and shale
- 4217 - 4530 Lime
- 4530 RTD

STATE OF KANSAS)
 COUNTY OF SEDGWICK)

SS.

RECEIVED
 JAN 8 1980
 STATE OF KANSAS

I, JAMES C. REMSBERG, OF THE **SLAWSON DRILLING COMPANY, INC.**
 UPON OATH STATE THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE
 LOG OF THE #2 Broughton 'G' TEST.

James C. Remsberg

 JAMES C. REMSBERG, Engineer

SUBSCRIBED AND SWORN TO BEFORE ME THIS 24th DAY OF January, 1980.

Sherry L. Kendall

 SHERRY L. KENDALL, Notary Public

MY COMMISSION EXPIRES : 6/12/82

