

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-101-21,111-10-00

LEASE NAME M. Dodge

WELL NUMBER 1

SPOT LOCATION NW/NW/NW

SEC. 1 TWP. 19S RGE. 29E XXXXXX(W)

COUNTY Lane

Date Well Completed 1-16-85

Plugging Commenced 1-16-85

Plugging Completed 1-16-85

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Stauffer Oil & Gas, Inc.

ADDRESS P. O. Box 6; Liberal, KS 67901

PHONE # (316) 624-3767 OPERATORS LICENSE NO. 9641

Character of Well D & A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing formation N/A Depth to top -- bottom -- T.D. 2898'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS N/A

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface	Fresh Water	150	175	8 5/8"	261'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. 60/40 Poz, 2% gel, 2% CaCl<sub>2</sub>  
50 sx from 2150-2000, mud to 1260, 40 sx from 1260-1160, mud to 500', 50' sx from 300-200,  
mud to 40', 10 sx from 40-3', 10 sx in rathole, 10 sx in mousehole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. --  
Address Ness City, KS


RECEIVED  
STATE CORPORATION COMMISSION

STATE OF KANSAS COUNTY OF SEWARD, ss.

R. F. Burke, Agent (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R F Burke

(Address) P.O. Box 6; Liberal, KS 67901



SUBSCRIBED AND SWORN TO before me this 22nd day of January, 1985

A. J. Parnell  
Notary Public

My Commission expires: 7-7-85