

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-21, 762-00-00

LEASE NAME Palmer Trust

WELL NUMBER 1

1685 Ft. from N Section Line

1671 Ft. from E Section Line

SEC. 1 TWP. 19 SRGE. 28 (E) or (W)

COUNTY Lane

Date Well Completed 05-11-98

Plugging Commenced 05-09-98

Plugging Completed 05-11-98

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Ritchie Exploration, Inc.

ADDRESS P O Box 783188, Wichita, Ks. 67278-3188

PHONE (316) 691-9500 OPERATORS LICENSE NO. 4767

Character of Well D/A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 05-07-98 (date)

by Gary Winters, Dodge City (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

05-20-1998

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface				8 5/8"		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set
1st plug from 2150'-1950' w/50 sks, 2nd plug from 1220'-90' w/80 sks, 3rd plug from 610'-450' w/40 sks, 4th plug from 230'-70' w/50 sks, 5th plug from 40'-top w/10 sks, 15 sks rathole, total 245 sks 60/40 pos. 6% gel with 1/4# floseal/sk.

Name of Plugging Contractor Abercrombie RTD, Inc. License No. 30684

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Ritchie Exploration, Inc. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) [Signature]

(Address) _____

SUBSCRIBED AND SWORN TO before me this 19th day of May, 19 98

Julie K. Stout
Notary Public

JULIE K. STOUT
Notary Public, State of Kansas
My Appt. Expires 7-23-2001

Expires: July 23, 2001