STATE OF KANSAS STATE CORPORATION COMMISSION 200 Colorado Derby Building Wichita, Kansas 67202

Character of Well D&A

WELL PLUGGING RECORD K.A.R.-82-3-117

API NUMBER 15-101-21,570-00-00

LEASE	NAME_	Nelson	Schwartz
-------	-------	--------	----------

TYPE OR PRINT NOTICE: Fill out completely and return to Cons. Div. office within 30 days.

WELL NUMBER 1 990' Ft. from S Section Line

990' Ft. from E Section Line SEC. 25 TWP.195 RGE. 28 XENOR (W)

COUNTY ____Lane

Date Well Completed 3-12-91

Plugging Commenced 3-12-91

Plugging Completed 3-12-91

17-21-1000

The	plugging proposal	was approved	On	March 12, 1991	(etab)
by _	Steve	Pfeifer		(KCC District Agent's	Name).

Is ACO-1 filed? NO ____ If not, is well log attached? NO ____

Producing Formation Depth to Top Bottom T.D. 46501

Show depth and thickness of all water, oil and gas formations.

STATE CG: STATE CG:

LEASE OPERATOR Ritchie Exploration, Inc.

ADDRESS 125 N. Market - #1000, Wichita, KS 67202

PHONE# (316) 267-4375 OPERATORS LICENSE NO. 4767

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

OIL, GAS OR WATER RECORDS		CASING RECORD				RD	.002/ 177)		
							MAR 2.1 10.64		
Formation	Content	From	To	Size	Put In	Pulled	out		
	1	})	8 5/8"	201'	_None	COMS1		
		1		f			Michila Page 1994		
			1						
				1					
		1	<u> </u>	·]				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Spotted 50 sx. cement at 2065' thru drill pipe. Spotted 10 sx. w/ plug @ 40'. Spotted 80 sx. cement at 1250' thru drill pipe. 15 sx. in rathole.

Spotted 50 sx. cement at 625' thru drill pipe. Spotted 40 sx. cement at 230' thru drill pipe.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor White & Ellis Drilling, Inc. License No. 5420

Address 401 E. Douglas - Suite 500, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES:

COUNTY OF SEDGWICK STATE OF KANSAS

Michael L. Considine (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Michael & Considere

401 E. Douglas - Suite 500 (Address) Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 12th day of March . 19 91


CAROLYN J. TJADEN Notary Public

NOTARY PUBLIC My Commission Expirés: My Annt Fyn Cont 5 1002 STATE OF KANSAS

MAR 1 9 1991

25 74-28 W

MAR , 0 102



WHITE

AND ELLIS DRILLING, Inc.

1143 2 0 15ml

DRILLERS LOG

OPERATOR:	Wichita, White & F		17202 Ling, In	, 125 N. Ma c. 401 E. I			500	
Lease Name	Nelson S	chwartz			Well	Well No. 1		
Sec. 25	т	195	R	28 <u>W</u>	_ Spot	NW SE	SE	
County Lar								
Casing Record		3 11	e 20	1' wit	h	135	sx.	
Producti	-						sx.	
Type Well:								
Drilling Comm	enced 3	-4-91	Dri]	ling Compl	eted _	3-12-91		
Formation		From	To		T	ops		
Cellar Shale Shale & Sands Shale Sand Shale Lime & Shale Shale & Lime Lime & Shale Chert & Lime		0 5 400 1410 1540 1755 2810 3485 3925 4355	5 400 1410 1540 1755 2810 3485 3925 4355 4650	•				