

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-101-21,279-00-00

LEASE NAME Starr

WELL NUMBER #1

3630' Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 23 TWP. 19 RGE. 28 (E) or (W)

COUNTY Lane

Date Well Completed \_\_\_\_\_

Plugging Commenced 12-23-86

Plugging Completed 12-30-86

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Blue Goose Drilling Co., Inc.

ADDRESS Box 1413, Great Bend, Kansas 67530

PHONE # 816-793-8170 OPERATORS LICENSE NO. 5104

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? One (1)

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? With application

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4700'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	304'	None
				5-1/2"	4400'	2,205.11'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Dumped sand to 4250' and 5 sacks cement. Shot casing at 3600', 3000', 2800', 2500' and 2200'. Pulled 53 joints of 5-1/2" casing. Allied squeezed well with 3 sacks hulls, 15 sacks gel, 50 sacks cement, 10 sacks gel, 1 sack hulls, released plug and pumped 165 sacks 60/40 posmix cement with 6% added gel and 3% calcium chloride. Maximum pressure was 500 psi and shutin 200 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct.

STATE CORPORATION COMMISSION

01-01-1987  
 JAN 1 1987

(Signature) James W. Rockhold

(Address) James W. Rockhold  
 Box 698, Gr. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 31st day of December, 19 86


CONSERVATION DIVISION  
 WICHTA, KANSAS

My Commission Expires:

IONA M. LEATHERMAN  
 Barton County, Kansas  
 My Appt. Exp. 4-26-87

Iona M. Leatherman  
 Notary Public

15-101-21279-00-00



**ELECTRA  
LOG  
INC.**

Sec. 23 Twp. 19s Rge. 28w

*Radiation Guard Log*

# 8912	COMPANY	Blue Goose Orlg		
	WELL	Starr #1		
	FIELD			
	COUNTY	Lane	STATE Kansas	
	Location	NE-SE-NW		Other Services
	Sec.	23	Twp.	19s Rge. 28w

Permanent Datum	Ground Level	Elev	2757
Log Measured From	K.B. 7.0	ft Above Perm. Datum	
Depth Measured From	Kelly Bushing		
		Elev	K.B. 2764
		DI	
		G.I.	2757

Date	1-22-86		
Run No	one		
Depth - Drive	4700		
Depth - Loggs	4705		
Blow Log Log	4702		
Top Log	0		
Casing - Drive	8 1/2" @ 300		
Casing - Loggs	306		
Bit Size	7 7/8		
Flow Fluid in Hole	Low Solids CL 7,000		
Dens.   Visc	9.6   43		
pH   Fluid Loss	8.0   10.0 ml		
Source of Sample	Flowline		
Rtg Meas Temp	.80 @ 52	1	@
Rtg Meas Temp	.73 @ 52	1	@
Rtg Meas Temp	.76 @ 52	1	@
Source Rtg Rtg	Charts		@
Rtg BHT	.34 @ 122	1	@
Time Since Circ	2 hrs		
Max Rec Temp	122		
Equip   Location	143   G.B.		
Recorded By	M Jacobs A Cape		
Witnessed By	Mr. Pete Moreland Mr. Martin Miller		

FIELD  
PRINT

RECEIVED  
 STATE OF KANSAS  
 COMMISSIONER OF REVENUE  
 JUL 12 '86