

KCC OIL/GAS REGULATORY OFFICE

ALT2

DATE Sept. 23 & 24, 1996

- New Situation
- Response to Request
- Follow-up

OPERATOR Cambron, Paul L. # 30104

NAME 118 N. Penn, P.O. Box 384

LOCATION NE SW SE, SEC 1, T 17, S, R. 22 ^{NE} _W

& ADDRESS Ness City, KS 67560

LEASE Barber Well # 1-1

PHONE NO. 913-798-2282 OTHER _____

COUNTY Ness API# 15-135-23,872-00-00

REASON FOR INVESTIGATION: Alternate II cementing

PROBLEM: Alternate II cementing not completed.

10-1-96

PERSON(S) CONTACTED: Moe Smith w/Cambron

FINDINGS: 9/23/96-Richard Lacey went to the location to witness the Alternate II cementing.

Port collar set at 1613'. Opened port collar and pumped 180 sx Midcon Cement. Circulated 5 bbls. of water to pit and lost circulation. Cement did not circulate.

9/24/96-Kevin Strube back on location. L & K perforated at 775'. Halliburton pumped

125 sx Halliburton Lite cement. Let set 35 minutes. Pumped 50 sx common cement w/3% cc.

Pumping 1/2 bbl. per minute. Started circulating. Circulated cement to surface. 175 sx total.

Maximum pressure 1700 psi and shut in 900 psi.

ACTION/RECOMMENDATIONS: Alternate II cementing completed. photos taken: _____

Retain 1 copy Joint District Office
Send 1 copy Conservation Division

By Kevin Strube
9/24/96

LEASE INSPECTION

COMPLAINT

FIELD REPORT X