

API NUMBER 15-101-20929 *0004*

LEASE NAME Larry

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

SW NE SW Ft. from S Section Line

 Ft. from E Section Line

SEC. 21 TWP. 19 RGE. 28W (E) or (W)

COUNTY Lane

Date Well Completed

Plugging Commenced 1-7-87

Plugging Completed 1-9-87

LEASE OPERATOR Palomino Petroleum

ADDRESS Route 5 Box 51-C Newton, Kansas 67114

PHONE# (316) 283-0232 OPERATORS LICENSE NO. 5161

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Richard Lacy

Is ACO-1 filed? yes if not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4725

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	300	none
				5 1/2	4720	823

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pump 1 sk. of hulls & 20 sks. of cement @ 4200

Pump 60 sks. of cement @ 600

Pump 50 sks. of cement @ 350

Put 10 sks. of cement @ 40 to 0 Cut off & cap 8 5/8 3' below ground level

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address Box 506 Liberal, Kansas 67901

STATE OF Kansas COUNTY OF ~~Sevier~~ Harvey, ss.

Bob Watchous

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Bob Watchous

(Address) Route 5 Box 51-C
Newton, Kansas 67114

SUBSCRIBED AND SWORN TO before me this 23rd day of January, 19 87

Kathryn L. Frerking
Notary Public

My Commission Expires: August 21, 1989



FEB 5 1987
02-05-1987
CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG
LARRY #1
SW NE SW
Sec. 21-19S-28W
Lane County, Kansas

15-101-20929-00-00

Company: Palomino Petroleum

Contractor: BEREDCO INC.

Comm: 2/14/84

Comp.: 2/21/84

Casing: Surface: 7 jts., new, 24#, 8-5/8" Set @ 300' w/200 sks of 60-40 Pozmix 2% Gel, 3% CC. Did Circ. PD @ 8:30 PM, 2/15/84 by Sun Cementing.

Production: Set 115 jts., new, 14#, 5 1/2" Set @ 4720' w/200 sks of 60-40 Pozmix, 2% Gel, 10% Salt, 15 bbls. of Salt Flush. PD @ 8:00 PM, 2/21/84 by Allied.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Sand & Shale	0'	435'
Shale & Sand	435'	1103'
Sand & Shale	1103'	2005'
Lime & Shale	2005'	2730'
Lime	2730'	3235'
Lime & Shale	3235'	3430'
Lime	3430'	3610'
Lime & Shale	3610'	4409'
Lime	4409'	4625'
Lime & Shale	4625'	4725'


TOTAL ROTARY DEPTH 4725'

STATE OF KANSAS

ss:

COUNTY OF SEDGWICK

I certify that this is a true and correct copy of the above log as shown by the drilling reports.



BEREDCO

[Signature]

STATE CORPORATION COMMISSION

DEC 30 1983
12-30-1983
CONSERVATION DIVISION
Topeka Kansas

Subscribed and sworn to before me this 29th day of February, 1984

[Signature: Cheryl L. Benoit]