

STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

K.A.R.-82-3-117

API NUMBER 101-217670000

LEASE NAME Thomas "A"

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

1,650 Ft. from <sup>N</sup> Section Line

2,310 Ft. from <sup>W</sup> Section Line

SEC. 17 TWP. 19 RGE. 28 (E) or (W)

COUNTY Lane

Date Well Completed 6-18-99

Plugging Commenced 6-18-99

Plugging Completed 6-18-99

LEASE OPERATOR Trans Pacific Oil Corporation

ADDRESS 100 S. Main, Ste. 200, Wichita, KS. 67202

PHONE#(316) 262-2596 OPERATORS LICENSE NO. 9408

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-18-99 (date)

by Gary Winters (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.O. 4,700'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	205'	Cmt'd. w/150 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each section. Push bridge plug to 2,200', spot 50 sax cement on plug; push bridge plug to 1,200', spot 80 sax cement on plug; push bridge plug to 650', spot 40 sax cement on plug; push bridge plug to 240', spot 30 sax cement on plug; push wiper plug to 40', dump 10 sax cement on plug to cellar; dump 15 sax cement down rat hole and 10 sax cement down mouse hole.

Name of Plugging Contractor Shields Drilling Co. License No. 5184

Address PO Box 709, Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Trans-Pacific Oil Corporation

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec/-Treas (Employee of Operator) or (Director) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) PO Box 709, Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 30th day of June, 1999

NOTARY PUBLIC - State of Kansas  
JILL A. JONES  
My Appt. Exp. 4-30-2002

My Commission Expires: 4-30-2002

Jill A. Jones  
Notary Public