

LEASE NAME Thomas

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1

4290 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 17 TWP. 19S RGE. 28 ~~XXXX~~ (W)

COUNTY Lane

LEASE OPERATOR Energy Exploration, Inc.

ADDRESS 1002 S. Broadway, Wichita, KS 67211

PHONE# (316) 267-7336 OPERATORS LICENSE NO. 5063

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-21-88 (date)

by State Pluggger, Dwayne Rankin District Agent's Name).

Is ACO-1 filled? NO If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom T.D. 4686'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	261'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
 Circulate heavy mud in the hole. 1st plug from 2140' to 1940' w/50 sx. 2nd plug from 1330' to 1010' w/80 sx, 2 sx of hulls. 3rd plug from 300' to 100' w/50 sx. 4th plug from 40' to surface w/10 sx. Rathole 15 sx. All cement 60/40 posmix, 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 801 Union Center, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Energy Exploration, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 801 Union Center

Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 2nd day of December, 19 88

Janet A. Stuck
 Notary Public

My Commission Expires: 12-29-90

