

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-21,183-00-00

LEASE NAME Stormont

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1

2310 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 15 TWP. 19 RGE. 28 (E or W)

COUNTY Lane

Date Well Completed 7-18-85

Plugging Commenced 8:00 AM

Plugging Completed 10:00 AM

LEASE OPERATOR Palomino Petroleum

ADDRESS P.O. Box 18610

PHONE# (316) 683-8152 OPERATORS LICENSE NO. 5161

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #1 Dodge City KS

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation D & A Depth to Top _____ Bottom _____ T.O. 4670'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Sand & Shale	Surface hole	0		8 5/8	237.91	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Plug @ 2120'-50 sx, plug @ 1200'-80 sx, plug @ 300'-50 sx, plug @ 40'-solid bridge & 10 sx, plug @ rathole-15 sx.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor DNB Drilling, Inc. License No. 5476

Address 535 N. Oliver Wichita, KS 67208

STATE OF Kansas COUNTY OF Sedgwick, ss.

R. W. Watchous (XXXXXXXXXXXXXXXXXXXX) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]


(Address) P. O. Box 18610, Wichita, KS 67218

SUBSCRIBED AND SWORN TO before me this 2nd day of August, 19 85

Michael M. Shockley
Notary Public

My Commission Expires: Jan 30 1988

STATE CORPORATION COMMISSION



AUG 5 1985 Form CP-4
08-05-1985 Revised 08-84
CONSERVATION DIVISION

15-101-21183-00-00

D N B Drilling, Inc.



J. L. DONELSON, PRES.
(316) 687-5471

ROTARY CONTRACTOR DRILLING DEALS

535 NORTH OLIVER

WICHITA, KANSAS 67208

DRILLERS' LOG

Palomino Petroleum
P.O. Box 18610
Wichita, KS 67218

Stormont #1
NW NE SE Sec.15-19-28W
Lane Co., KS

Commenced: 7-9-85
Completed: 7-18-85

Surface casing: Ran 6 jts. 8 5/8", 20# new casing. Set @ 246'.
Cemented with 200 sx 60/40 pozmix, 2% gel, 3% cc.
Cement did circulate.

FORMATION

Sand & Shale
Anhydrite
Shale
Shale & Lime
Lime

DEPTH

0-1860
1860-2315
2315-3000
3000-3575
3575-4670 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

DNB Drilling, Inc.

By *J. L. Donelson*


STATE OF KANSAS: ss:

Subscribed and sworn to before me this 22nd day of July, 1985.

Vicky L. Coppage, Notary Public

My appointment expires:
May 28, 1989

Vicky L. Coppage



RECEIVED
STATE CORPORATION COMMISSION

AUG 5 1985
08-05-1985
CONSERVATION DIVISION
Wichita, Kansas