

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-23,695-00-00

LEASE NAME Zeller #1

WELL NUMBER 1

990 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 5 TWP. 16SRGE. 21 (W)

COUNTY Ness

Date Well Completed 8/23/92

Plugging Commenced 8/23/92

Plugging Completed 8/23/92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Mid-Continent Resources, Inc.

ADDRESS P. O. Box 399, Garden City, KS 67846

PHONE#(913) -398-2270 OPERATORS LICENSE NO. 8996

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-23-92 (date)

by Duane Ranken (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4360'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	208'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Mud laden fluid 4360'01720' 10 sks cement @ 40'
50 sks cement @ 1720' 10 sks in mousehole
80 sks cement @ 860' 15 sks in rathole
50 sks cement @ 240'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address P. O. Box 506, Russell, KS 67665-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mid-Continent Resources, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Kyle B. Branum (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
Kyle B. Branum
 (Address) Box 506, Russell, KS

SUBSCRIBED AND SWORN TO before me this 24th day of August 1992

Glenda R. Tiffin
 Glenda R. Tiffin, Notary Public
 STATE CORPORATION COMMISSION
 WICHITA, KANSAS

GLENDA R. TIFFIN
 NOTARY PUBLIC
 STATE OF KANSAS
 MY APPT. EXPIRES 2-6-96

15-135-23695-00-00

EMPHASIS OIL OPERATIONS

P. O. BOX 506

RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: Mid-Continent Resources, Inc.
P. O. Box 399
Garden City, Kansas 67846

CONTRACTOR: Emphasis Oil Operations
Box 506
Russell, KS 67665

LEASE: Zeller

WELL #1

LOCATION: C N/2 SE SE
Section 5-16S-21W
Ness County, Kansas

LOGGERS TOTAL DEPTH: 4359'

ROTARY TOTAL DEPTH: 4360'

COMMENCED: 8/14/92

CASING: 8-5/8" @ 208' w/135 sks cement

ELEVATION: 2355' K.B.

COMPLETED: 8/23/92

STATUS: Dry Hole


DEPTHS & FORMATIONS

(All measurements from K.B.)

Dakota Sand	990'	Heebner	3746'
Cedar Hills	1080'	Lansing-Kansas City	3787'
Shale	1367'	Pawnee	4149'
Anhydrite	1678'	Mississippi	4309'
Shale	1713'	R.T.D.	4360'


STATE OF KANSAS)
) ss
COUNTY OF RUSSELL)


Kyle B. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.


Kyle B. Branum

Subscribed and sworn to before me on August 24, 1992.

My commission expires: February 6, 1996.


GLENDA R. TIFFIN
NOTARY PUBLIC
STATE OF KANSAS
MY APPT. EXPIRES 2-6-96


Glenda R. Tiffin, Notary Public
RECEIVED
STATE CORPORATION COMMISSION
AUG 25 1992

CONSERVATION DIVISION
Wichita, Kansas
08-25-1992